

ARIZONA DEPARTMENT OF TRANSPORTATION
INTERMODAL TRANSPORTATION DIVISION
CONTRACTS AND SPECIFICATIONS SECTION

BID SCHEDULE

CONTRACT # 1999147

TRACS No.	Project No.	Item	County	District	Gross Length	Net Length	Prepared By:
060 GI 302 H468201C	STP 026-1-(47)	15700	GILA	GLOBE		11	Vergith Charles

Highway Termini	Location	Work Description
• GLOBE-SHOW LOW HWY. (US 60)	• MP 302.3-MP 313.3 EB & WB	• CST CLIMBING LANES

BID SCHEDULE

060 GI 302 H468201C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
2010011	CLEARING AND GRUBBING	ACRE	23		
2020010	REMOVAL OF STRUCTURAL CONCRETE (PIPE HEADWALL REMOVALS)	L.SUM	1		
2020019	REMOVAL OF EMBANKMENT CURB	L.FT.	1,731		
2020029	REMOVAL OF ASPHALTIC CONCRETE PAVEMENT	SQ.YD.	2,816		
2020041	REMOVAL OF PIPE	L.FT.	272		
2020053	REMOVE (INLET & SPILLWAY)	EACH	4		
2020060	REMOVE AND SALVAGE (SRT-350)	EACH	1		
2020065	REMOVAL OF TREES	EACH	14		
2020071	REMOVE GUARD RAIL	L.FT.	2,138		
2020084	REMOVE BITUMINOUS PAVEMENT (MILLING) (2 1/2")	SQ.YD.	1,813		
2020101	REMOVE FENCE	L.FT.	1,000		
2020201	SAW CUTTING	L.FT.	25,344		
2020402	REMOVE AND RESET (SIGNS)	L.SUM	1		
2030301	ROADWAY EXCAVATION	CU.YD.	100,400		
2030401	DRAINAGE EXCAVATION	CU.YD.	73		

BID SCHEDULE

060 GI 302 H468201C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
2070001	DUST PALLIATIVE	M.GAL.	2,500	\$11.00	\$27,500.00
2080001	SEPARATION GEOTEXTILE FABRIC	SQ.YD.	18,400		
3030022	AGGREGATE BASE, CLASS 2	CU.YD.	5,643		
3030025	AGGREGATE SUBBASE, CLASS 5	CU.YD.	18,760		
3060001	GEOGRID BASE REINFORCEMENT	SQ.YD.	18,400		
4040111	BITUMINOUS TACK COAT	TON	11		
4040116	APPLY BITUMINOUS TACK COAT	HOUR	18		
4090005	ASPHALTIC CONCRETE (MISCELLANEOUS STRUCTURAL) (SPECIAL MIX)	TON	8,919		
4140040	ASPHALTIC CONCRETE FRICTION COURSE (ASPHALT-RUBBER)	TON	968		
4140042	ASPHALT RUBBER MATERIAL (FOR AR-ACFC)	TON	92		
4140044	MINERAL ADMIXTURE (FOR AR-ACFC)	TON	10	\$90.00	\$900.00
5010011	PIPE, CORRUGATED METAL, 24"	L.FT.	454		
5010017	PIPE, CORRUGATED METAL, 30"	L.FT.	44		
5010025	PIPE, CORRUGATED METAL, 36"	L.FT.	520		
5010035	PIPE, CORRUGATED METAL, 48"	L.FT.	98		

BID SCHEDULE

060 GI 302 H468201C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
5014024	FLARED END SECTION, 24" (C-13.25)	EACH	11		
5014030	FLARED END SECTION, 30" (C-13.25)	EACH	1		
5014036	FLARED END SECTION, 36" (C-13.25)	EACH	7		
6016088	HEADWALL (DETAIL C: SLOPE PROTECT FOR 2-36" PIPES)	EACH	3		
6016090	HEADWALL (B-11.12)	EACH	1		
6016091	HEADWALL (B-11.13)	EACH	2		
6070038	SLIP BASE (2 1/2" SQUARE TUBE POST)	EACH	38		
6070041	SIGN POST (P-1) (PERFORATED) (SINGLE)	L.FT.	613		
6070042	SIGN POST (P-2) (PERFORATED) (TELESCOPING)	L.FT.	96		
6070046	FOUNDATION FOR SIGN POST (P-1)(PERFORATED)	EACH	51		
6070047	FOUNDATION FOR SIGN POST (P-2)(PERFORATED)	EACH	7		
6080002	REGULATORY, WARN, OR MARKER SIGN PANEL W/TYP II SHEET	SQ.FT.	301		
6080101	MISCELLANEOUS WORK (SIGNS)	L.SUM	1		
7015010	TEMPORARY CONCRETE BARRIER (INSTALLATION AND REMOVAL)	L.FT.	2,363		

BID SCHEDULE

060 GI 302 H468201C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
7015052	OBLITERATE PAVEMENT MARKING (STRIPE)	L.FT.	38,077		
7016020	TEMPORARY CONCRETE BARRIER (IN USE)	L.FT./DAY	99,225		
7016030	BARRICADE (TYPE II, VERT.PANEL, TUBULAR MARKER)	EACH-DAY	67,374		
7016031	BARRICADE (TYPE III, HIGH LEVEL FLAG TREES)	EACH-DAY	650		
7016033	PORTABLE SIGN STANDS (SPRING TYPE)	EACH-DAY	2,768		
7016035	WARNING LIGHTS (TYPE A)	EACH-DAY	4,214		
7016036	WARNING LIGHTS (TYPE B)	EACH-DAY	3,850		
7016037	WARNING LIGHTS (TYPE C)	EACH-DAY	67,374		
7016038	TRAFFIC CONE (28 INCHES)	EACH-DAY	2,500		
7016039	EMBEDDED SIGN POST	EACH-DAY	9,340		
7016045	TEMPORARY SIGN (TYPE III/IV)(LESS THAN 10 S.F.)	EACH-DAY	3,650		
7016046	TEMPORARY SIGN (TYPE III/IV)(GREATER THAN 10 S.F.)	EACH-DAY	4,188		
7016071	PILOT VEHICLE WITH DRIVER	HOURL	680		
7016075	FLAGGING SERVICES (CIVILIAN)	HOURL	1,808		
7016078	FLAGGING SERVICES (LOCAL ENFORCEMENT OFFICER)	HOURL	1,800		

BID SCHEDULE

060 GI 302 H468201C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
7030003	DELINEATOR (4-M-4.01) (SINGLE WHITE OR SINGLE YELLOW)	EACH	28		
7030022	DELINEATOR (FLEXIBLE) (SINGLE WHITE OR SINGLE YELLOW)	EACH	30		
7040070	PAVEMENT MARKING (WHITE THERMOPLASTIC) (SPRAYED) (0.030")	L.FT.	32,654		
7040071	PAVEMENT MARKING (YELLOW THERMOPLASTIC) (SPRAYED) (0.030")	L.FT.	36,027		
8050003	SEEDING (CLASS II)	ACRE	11		
9010001	MOBILIZATION	L.SUM	1		
9030011	BARBED WIRE FENCE, TYPE 1	L.FT.	1,000		
9031003	TEMPORARY FENCE (TYPE 4) (WOVEN WIRE) (MODIFIED)	L.FT.	1,288		
9050001	GUARD RAIL, W-BEAM, SINGLE FACE	L.FT.	2,900		
9050018	GUARD RAIL TERMINAL (SRT-350 OR FLEAT-350)	EACH	3		
9050036	GUARD RAIL, ANCHOR ASSEMBLY	EACH	3		
9050047	RECONSTRUCT GUARD RAIL END TERMINAL ASSEMBLY	EACH	1		
9130051	RIPRAP (DUMPED) (D50 = 6")	CU.YD.	102		
9130052	RIPRAP (DUMPED) (D50=9")	CU.YD.	116		

BID SCHEDULE

060 GI 302 H468201C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
9160001	EMBANKMENT CURB	L.FT.	2,161		
9170001	EMBANKMENT SPILLWAY (C-4.10)	L.FT.	228		
9170021	INLET (C-4.10) (SINGLE)	EACH	4		
9230001	PROVIDE ON-THE-JOB TRAINING	HOUR	1,000	\$.80	\$800.00
9240018	FORCE ACCOUNT WORK (STORM WATER POLLUTION PREVENTION)	L.SUM	1	\$65,000.00	\$65,000.00
9240170	CONTRACTOR QUALITY CONTROL	L.SUM	1		
9250001	CONSTRUCTION SURVEYING AND LAYOUT	L.SUM	1		

BID SCHEDULE

060 GI 302 H468201C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
STA. 1130+78.75 BOX CULVERT EXTENSION					
2020009 A	REMOVAL OF STRUCTURAL CONCRETE	CU.YD.	23		
2030501 A	STRUCTURAL EXCAVATION	CU.YD.	145		
2030506 A	STRUCTURE BACKFILL	CU.YD.	135		
6010002 A	STRUCTURAL CONCRETE (CLASS S) (F'C = 3,000)	CU.YD.	52		
6050002 A	REINFORCING STEEL	LB.	7,945		
6050101 A	PLACE DOWELS	EACH	6		

BID SCHEDULE

060 GI 302 H468201C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
STA. 1142+51.12 BOX CULVERT EXTENSION					
2020009 B	REMOVAL OF STRUCTURAL CONCRETE	CU.YD.	16		
2030501 B	STRUCTURAL EXCAVATION	CU.YD.	105		
2030506 B	STRUCTURE BACKFILL	CU.YD.	210		
6010002 B	STRUCTURAL CONCRETE (CLASS S) (F'C = 3,000)	CU.YD.	41		
6050002 B	REINFORCING STEEL	LB.	5,890		
6050101 B	PLACE DOWELS	EACH	6		

BID SCHEDULE

060 GI 302 H468201C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
STA. 1233+64.72 BOX CULVERT EXTENSION					
2020009 C	REMOVAL OF STRUCTURAL CONCRETE	CU.YD.	9		
2030501 C	STRUCTURAL EXCAVATION	CU.YD.	7		
2030506 C	STRUCTURE BACKFILL	CU.YD.	35		
6010002 C	STRUCTURAL CONCRETE (CLASS S) (F'C = 3,000)	CU.YD.	14		
6050002 C	REINFORCING STEEL	LB.	1,355		
6050101 C	PLACE DOWELS	EACH	5		

BID SCHEDULE

060 GI 302 H468201C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
STA 117+00.00 BOX CULVERT EXTENSION (STRUCTURE NO. 4157)					
2020009 D	REMOVAL OF STRUCTURAL CONCRETE	CU.YD.	60		
2030501 D	STRUCTURAL EXCAVATION	CU.YD.	265		
2030506 D	STRUCTURE BACKFILL	CU.YD.	300		
6010002 D	STRUCTURAL CONCRETE (CLASS S) (F'C = 3,000)	CU.YD.	139		
6050002 D	REINFORCING STEEL	LB.	17,765		
6050101 D	PLACE DOWELS	EACH	16		

BID SCHEDULE

060 GI 302 H468201C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
STA. 133+07.48 BOX CULVERT EXTENSION					
2020009 E	REMOVAL OF STRUCTURAL CONCRETE	CU.YD.	30		
2030501 E	STRUCTURAL EXCAVATION	CU.YD.	155		
2030506 E	STRUCTURE BACKFILL	CU.YD.	210		
6010002 E	STRUCTURAL CONCRETE (CLASS S) (F'C = 3,000)	CU.YD.	49		
6050002 E	REINFORCING STEEL	LB.	7,095		
6050101 E	PLACE DOWELS	EACH	6		

BID SCHEDULE

060 GI 302 H468201C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
STA. 203+10.19 BOX CULVERT EXTENSION					
2020009 F	REMOVAL OF STRUCTURAL CONCRETE	CU.YD.	7		
2030501 F	STRUCTURAL EXCAVATION	CU.YD.	20		
2030506 F	STRUCTURE BACKFILL	CU.YD.	55		
6010002 F	STRUCTURAL CONCRETE (CLASS S) (F'C = 3,000)	CU.YD.	25		
6050002 F	REINFORCING STEEL	LB.	2,920		
6050101 F	PLACE DOWELS	EACH	10		

BID SCHEDULE

060 GI 302 H468201C

Item No.	Item Description	Unit	Quantity	Unit Price	Extended Amount
STA. 215+60.94 BOX CULVERT EXTENSION					
2020009 G	REMOVAL OF STRUCTURAL CONCRETE	CU.YD.	12		
2030501 G	STRUCTURAL EXCAVATION	CU.YD.	15		
2030506 G	STRUCTURE BACKFILL	CU.YD.	130		
6010002 G	STRUCTURAL CONCRETE (CLASS S) (F'C = 3,000)	CU.YD.	45		
6050002 G	REINFORCING STEEL	LB.	5,600		
6050101 G	PLACE DOWELS	EACH	10		

BID TOTAL :